

6<sup>th</sup> October, 2020.

REF: GDC/MSD/005/2020:2020/pk-maf

TO: ALL BIDDERS

Dear Sir/Madam,

**ADDENDUM 1: REQUEST FOR CLARIFICATION**

**RE: TENDER FOR SUPPLY, INSTALLATION AND COMMISSIONING OF WEIGHBRIDGE FOR BARINGO-SILALI GEOTHERMAL PROJECT.**

In response to bidder's request for clarification, GDC wishes to provide the following clarification;

**Bidder's Question 1**

Please clarify on the specification on the containerized weigh office on requirements like container size, rooms/ partitioning, Air conditioning unit, wall sockets, lighting and furniture required and other required office features.

**GDC Response**

**Size:**

Standard 20 foot shipping container dimensions

**Insulation:**

1. Inner lining of styrofoam throughout the walls and ceiling.
2. Outer lining of 9 mm gypsum boards

**Electrical wiring:**

1. Complete electrical wiring for lighting system, 4 output sockets, security lighting.
2. Data cables

**Doors and windows:**

1. Steel door with lock
2. Top hang steel windows which open to reveal sliding glass windows.
3. Sliding glass windows shall have insect screen
4. Front window shall be wide enough to give unobstructed view of the weighbridge area

**Air conditioning:**

Install appropriate split air conditioning unit

Expected occupancy during operation is two (2) people.

**Floor:**

Shall be made of abrasion- resistant, anti-slip and water-resistant material.

**Colour:**

Shall be painted white externally

No furniture is required for the office.

N/B: All other instructions including the closing date of **Tuesday 13<sup>th</sup> October, 2020 at 2.00PM** remain unchanged.

Yours faithfully,



**DORIS KYAKA**  
**MANAGER, SUPPLY CHAIN**  
**FOR: GEOTHERMAL DEVELOPMENT COMPANY**